

平成29年度

林道五知・恵利原線復旧工事

数 量 計 算 書

数量總括表

[illegible]

土工計算書					
積込 (ルーズ)	土工数量計算書より			V = 143.1	
				= 143.1	m ³ 143.1
	地山土量換算	143.1 / 1.2		V = 119.2	
	積込量換算	119.2 × 0.9		V = 107.3	
	180 ° 旋回積込			= 107.3	m ³ 107.3
	119.2 - 107.3			V = 11.9	
	90 ° 旋回積込			= 11.9	m ³ 11.9
	143.1 × 16 % (別紙率案分)			V = 22.9	
				= 22.9	m ³ 22.9
残土処理	積込量換算値と同			V = 107.3	
				= 107.3	m ³ 107.3

土　工　数　量　計　算　書											
測点名	測点	距離 （m）	掘削・積込								
			面積 （㎡）	平均 （m）	量 （㎥）	面積 （㎡）	平均 （m）	量 （㎥）	面積 （㎡）	平均 （m）	量 （㎥）
A断面			0.00								
B断面		2.00	7.57	3.79	7.58						
C断面		5.00	11.10	9.34	46.70						
D断面		8.00	8.07	9.59	76.72						
E断面		3.00	0.00	4.04	12.12						
合計		18.00			143.12						

143.12