

土工計算書					
掘削	V=	標準断面図より 6.42 × 200.00 × 0.22	= 282.48		
			Σ = 282.48	m ³	282.5
土砂等運搬	V=	掘削より 282.48	= 282.48	m ³	
			Σ = 282.48	m ³	282.5

舗装工計算書				
アスファルト舗装工				
表層 (t=5cm)	標準断面図より A= 6.42 × 200.00	= 1284.00		
		Σ = 1284.00	m ²	1284.0
上層路盤 (M-30, t=10cm)	表層より A= 1284.00	= 1284.00		
		Σ = 1284.00	m ²	1284.0
下層路盤 (RC-40, t=12cm)	表層より A= 1284.00	= 1284.00		
		Σ = 1284.00	m ²	1284.0

区画線工計算書					
溶融式区画線 (白, 幅15cm, 実線)	(車道外側線)				
	L=	200.00	+	200.00	= 400.00
		左		右	
	(車道中央線)				
	L=	30.00			= 30.00
	No. 0～No. 1+10.0				
			Σ	=	430.00
	m				
	430.0				
溶融式区画線 (白, 幅15cm, 破線)	(車道中央線)				
	L=	85.00			= 85.00
	No. 1+10.0～No. 10				
			Σ	=	85.00
	m				
	85.0				
溶融式区画線 (白, 幅30cm, 実線)	(停止線)				
	L=	3.00			= 3.00
	No. 0付近 : 3.00				
			Σ	=	3.00
	m				
	3.0				
溶融式区画線 (黄, 幅15cm換算, 文字・記号)	(50km表示)				
	L=	18.60	×	1.00	= 18.60
	※50km : 18.6m/箇所				
			Σ	=	18.60
	m				
	18.6				

構造物撤去工計算書				
構造物取壊し工				
舗装版切断 (アスファルト) (t=15cm以下)	L= 6.20 + 9.40 + 200.00	= 215.60	m	
	※No.0横断：6.2m、No.10横断：9.4m No.0～No.10縦断：200.0m	Σ = 215.60	m	215.6
舗装版破碎 (アスファルト) (t=15cm以下)	A= 標準断面図より 6.42 × 200.00	= 1284.00		
		Σ = 1284.00	m ²	1284.0
運搬処理工				
殻運搬 (アスファルト)	V= 舗装版破碎より 1284.00 × 0.05	= 64.20		
		Σ = 64.20	m ³	64.2
殻処分 (アスファルト)	V= 殻運搬より 64.20	= 64.20		
		Σ = 64.20	m ³	64.2

仮設工計算書						
交通管理工						
交通誘導警備員A	N=	1.00	=	1.00	式	1.0
交通誘導警備員B	N=	1.00	=	1.00	式	1.0