

数 量 集 計 表 (1)							
工 種	種 別	細 別	規 格	単位	当 数 初 量		摘 要
市道今坂島茶屋線 1号箇所							
道 路 土 工				式	1		
	掘 削 工			式	1		
		掘 削		m <sup>3</sup>	240		
	残 土 処 理 工			式	1		
		積 込 み		m <sup>3</sup>	240		
		土 砂 等 運 搬		m <sup>3</sup>	240		
地 盤 改 良 工				式	1		
	路床安定処理工			式	1		
		路床安定処理工		m <sup>2</sup>	780		
舗 装 工				式	1		
	アスファルト 舗 装 工			式	1		
		表 層	再生密粒度アスコン TOP13, t=5cm	m <sup>2</sup>	780		
		上 層 路 盤	粒度調整碎石 M-30, t=12cm	m <sup>2</sup>	780		
		下 層 路 盤	再生切込碎石 RC-40, t=19cm	m <sup>2</sup>	780		
区 画 線 工				式	1		
	区 画 線 工			式	1		
		溶 融 式 区 画 線	白, 幅15cm, 実線	m	246		外側線
		溶 融 式 区 画 線	白, 幅15cm, 破線	m	62		中央線
構 造 物 撤 去 工				式	1		
	構造物取壊し工			式	1		
		舗 装 版 破 砕	アスファルト t=15cm以下	m <sup>2</sup>	780		
		舗 装 版 切 断	アスファルト t=15cm以下	m	140		

## 数量集計表 (2)

[illegible]

土 工 計 算 書

(一式当り)

掘削	V=	標準断面図より 1.96 × 123.00	=	241.08	m <sup>3</sup>	241.1
積込み	V=	掘削より 241.08	=	241.08	m <sup>3</sup>	241.1
土砂等運搬	V=	掘削より 241.08	=	241.08	m <sup>3</sup>	241.1

地盤改良工計算書

(一式当り)

路床安定処理工

安定処理工  
(セメント系固化材, t=30cm)

A= 表層より  
776.10

= 776.10

m<sup>2</sup>

776.1



舗 装 面 積 計 算 書											
測 点 名	測 点	距 離 (m)	表 層			路 盤			不 陸 整 正		
			幅 (m)	平 均 (m)	面 積 (m <sup>2</sup> )	幅 (m)	平 均 (m)	面 積 (m <sup>2</sup> )	幅 (m)	平 均 (m)	面 積 (m <sup>2</sup> )
NO. 0	NO. 0 + 0.00	0.00	6.35								
NO. 1	NO. 1 + 0.00	20.00	6.25	6.30	126.00						
NO. 2	NO. 2 + 0.00	20.00	6.30	6.28	125.60						
NO. 3	NO. 3 + 0.00	20.00	6.32	6.31	126.20						
NO. 4	NO. 4 + 0.00	20.00	6.35	6.34	126.80						
NO. 5	NO. 5 + 0.00	20.00	6.30	6.33	126.60						
NO. 6	NO. 6 + 0.00	20.00	6.30	6.30	126.00						
NO. 6+3.0	NO. 6 + 3.00	3.00	6.30	6.30	18.90						

区 画 線 工 計 算 書						(一式当り)	
溶融式区画線 (白, 幅15cm, 実線)	(車道外側線)						
	L=	123.00	×	2.00	=	246.00	m 246.0
溶融式区画線 (白, 幅15cm, 破線)	(車道中央線)						
	L=	61.50			÷	62.00	m 62.0

構 造 物 撤 去 工 計 算 書						(一式当り)	
構造物取壊し工							
舗装版破碎 (アスファルト) (t=15cm以下)	A=	表層より 776.10		=	776.10	m <sup>2</sup>	776.1
舗装版切断 (アスファルト) (t=15cm以下)	L=	6.35 + 6.30 + 123.00		=	135.65	m	135.7
		※No.0横断：6.35m、No.6+3.0横断：6.3m No.0～No.6+3.0縦断：123.0m					
運搬処理工							
殻運搬 (アスファルト)	V=	舗装版破碎より 776.10 × 0.05		=	38.81	m <sup>3</sup>	38.8
殻処分 (アスファルト)	V=	殻運搬より 38.81		=	38.81	m <sup>3</sup>	38.8





[illegible]

## 区 画 線 工 計 算 書

(一式当り)

溶融式区画線 (白, 幅15cm, 実線)	(車道外側線) L= 140.00 × 2.00	= 280.00	m	280.0
溶融式区画線 (白, 幅15cm, 破線)	(車道中央線・車道外側線) L= 70.00	= 70.00	m	70.0
区画線 (黄, 幅15cm, 実線)	(消火栓) L= 2.50	= 2.50	m	2.5

