


数 量 計 算 書															
道 路 等 除 草 業 務 (志 摩 町 地 内) 後 期															
除 草 業 務 総 延 長 (飛 石 防 護 無 し)	小計①		10,177		+	小計②		8,057		=	合計		18,234		m
除 草 業 務 総 面 積 (飛 石 防 護 無 し)	小計①		6,640.7		+	小計②		4,925.7		=	合計		11,566.4		㎡
縁 石 除 草 (飛 石 防 護 無 し)	小計①		1,357		+	小計②		658		=	合計		2,015		m
除 草 業 務 総 延 長 (飛 石 防 護 有 り)											合計②		6,230		m
除 草 業 務 総 面 積 (飛 石 防 護 有 り)											合計②		4,428.3		㎡
縁 石 除 草 (飛 石 防 護 有 り)											合計②		1,862		m
路線名	縁石除草					道路除草									
汐本7号線	[左]	18	m	42	m	[左]	82	m	259	m	[左]	53.4	㎡	160.3	㎡
	[右]	24	m			[右]	177	m			[右]	106.9	㎡		
汐本支線	[左]	22	m	38	m	[左]	100	m	206	m	[左]	70.0	㎡	144.2	㎡
	[右]	16	m			[右]	106	m			[右]	74.2	㎡		
汐本線	[左]	9	m	22	m	[左]	151	m	303	m	[左]	105.7	㎡	212.1	㎡
	[右]	13	m			[右]	152	m			[右]	106.4	㎡		
対上線	[左]		m	-	m	[左]	599	m	1,038	m	[左]	340.7	㎡	623.8	㎡
	[右]		m			[右]	439	m			[右]	283.1	㎡		
片田港線	[左]	48	m	108	m	[左]	517	m	1,005	m	[左]	346.5	㎡	654.7	㎡
	[右]	60	m			[右]	488	m			[右]	308.2	㎡		
名古屋線	[左]		m	15	m	[左]	202	m	376	m	[左]	141.4	㎡	263.2	㎡
	[右]	15	m			[右]	174	m			[右]	121.8	㎡		
一本松3号線	[左]		m	-	m	[左]	126	m	250	m	[左]	88.2	㎡	163.6	㎡
	[右]		m			[右]	124	m			[右]	75.4	㎡		
一本松1号線	[左]		m	124	m	[左]	526	m	1,175	m	[左]	362.8	㎡	780.7	㎡
	[右]	124	m			[右]	649	m			[右]	417.9	㎡		
奥山線(北)	[左]	14	m	61	m	[左]	500	m	920	m	[左]	324.0	㎡	598.8	㎡
	[右]	47	m			[右]	420	m			[右]	274.8	㎡		
奥山線(南)	[左]		m	-	m	[左]	317	m	716	m	[左]	219.9	㎡	458.6	㎡
	[右]		m			[右]	399	m			[右]	238.7	㎡		
藤原線	[左]	12	m	61	m	[左]	371	m	819	m	[左]	243.5	㎡	537.3	㎡
	[右]	49	m			[右]	448	m			[右]	293.8	㎡		
和具布施田1号線	[左]	101	m	373	m	[左]	625	m	1,093	m	[左]	429.5	㎡	691.7	㎡
	[右]	272	m			[右]	468	m			[右]	262.2	㎡		
長谷線	[左]		m	-	m	[左]	242	m	536	m	[左]	159.2	㎡	331.0	㎡
	[右]		m			[右]	294	m			[右]	171.8	㎡		
北線	[左]	103	m	103	m	[左]	170	m	341	m	[左]	119.0	㎡	238.7	㎡
	[右]	0	m			[右]	171	m			[右]	119.7	㎡		
間崎線	[左]	45	m	410	m	[左]	595	m	1,140	m	[左]	400.5	㎡	782.0	㎡
	[右]	365	m			[右]	545	m			[右]	381.5	㎡		
	[左]		m	-	m	[左]		m	-	m	[左]		㎡	-	㎡
	[右]		m			[右]		m			[右]		㎡		
	[左]		m	-	m	[左]		m	-	m	[左]		㎡	-	㎡
	[右]		m			[右]		m			[右]		㎡		
	[左]		m	-	m	[左]		m	-	m	[左]		㎡	-	㎡
	[右]		m			[右]		m			[右]		㎡		

[illegible]

防草対策工計算書	市道阿津里線			
防草シート工 (法面部)	A=	300.00	m ²	300.00

防草シート敷設工 単位数計算書 (100m²当り)



シートのラップ：重ね合せ10cm以上
アンカーピンの箇所にはテープ処理 (10cm×10cm) を行う

名 称	計 算 式	単位	数 量
防草シート チガヤシート 同等品	A= 120.0	m ²	120.0
U型アンカーピン 4本/m ²	N= 400.0	本	400.0
テープ チガヤテープ同等品 (ピン用テープ)	N= ※L=40m = 1.8	巻	1.8
ボンド シーリング材 「アタッチ」同等品	N= ※L=52m = 7.4	本	7.4