

土 工 計 算 書

(一式当り)

掘削

V= 舗装数量より
279.65 × 0.10 = 27.97 m3 28.0

残土処分

V= 27.97 + 0.00 - 0.00 / 0.90 = 27.97 m3 28.0

構 造 物 撤 去 工 計 算 書

(一式当り)

構造物取壊し工					
舗装版切断 (アスファルト) (t=15cm以下)	L=	16.00 + 5.10 No. 0 : 16.0m+No. 3+10.0 : 5.1m	=	21.10	m
					21.1
As取壊し	V=	舗装面積計算書より 279.65	=	279.65	m ³
					279.7
運搬処理工					
殻運搬 (As塊)	V=	As取壊しより 279.65 × 0.04	=	11.19	m ³
					11.2
殻処分 (As塊)	V=	殻運搬より 11.19	=	11.19	m ³
					11.2

舗 装 工 計 算 書

(一式当り)

アスファルト舗装工					
上層路盤工 (M-30, t=100)	A=	舗装面積計算書より 279.65	=	279.65	m ² 279.7
表層工 (top13 t=40)	A=	舗装面積計算書より 279.65	=	279.65	m ² 279.7

面積計算書 (舗 装 工)											
測 点 名	測 点	距 離 (m)	表 層			上 層 路 盤			下 層 路 盤		
			幅 (m)	平 均 (m)	面 積 (m ²)	幅 (m)	平 均 (m)	面 積 (m ²)	幅 (m)	平 均 (m)	面 積 (m ²)
NO. 0-7. 0	NO. 0 - 7. 00		0. 00			0. 00					
		16. 00		2. 10	33. 60		2. 10	33. 60			
NO. 0+9. 0	NO. 0 + 9. 00		4. 20			4. 20					
		11. 00		4. 05	44. 55		4. 05	44. 55			
NO. 1	NO. 0 + 20. 00		3. 90			3. 90					
		20. 00		3. 80	76. 00		3. 80	76. 00			
NO. 2	NO. 1 + 20. 00		3. 70			3. 70					
		20. 00		3. 95	79. 00		3. 95	79. 00			
NO. 3	NO. 2 + 20. 00		4. 20			4. 20					
		10. 00		4. 65	46. 50		4. 65	46. 50			
E. P.	NO. 3 + 10. 00		5. 10			5. 10					
合計		77. 00			279. 65			279. 65			0. 00

区画線工計算書

(一式当り)

区画線工					
側線 白色 実線 W=15cm	L= 図面より 16.00	=	16.00	m	16.0
停止線 白色 実線 W=30cm	L= 図面より 4.00	=	4.00	m	4.0
記号等 白色 実線 W=15cm換算	L= 18.60 ※18.6m/箇所	=	18.60	m	18.6

