

舖 装 工 計 算 書

(一式当り)

アスファルト舗装工

上層路盤工 (M-30, t=100)	A=	舗装面積計算書より 631.64	=	631.64	m2	631.6
表層工 (top13 t=40)	A=	舗装面積計算書より 631.64	=	631.64	m2	631.6

表層工 (top13 t=40)	A= 舗装面積計算書より 631.64	= 631.64	m2	631.6
---------------------	------------------------	----------	----	-------

面積計算書 (舗 装 工)											
測 点 名	測 点	距 離 (m)	表 層			上 層 路 盤					
			幅 (m)	平 均 (m)	面 積 (m2)	幅 (m)	平 均 (m)	面 積 (m2)			
No.0	No.0 0.00		3.12			3.12					
		7.80		4.97	38.77		4.97	38.77			
No.0+7.80	No.0 + 7.80		6.81			6.81					
		12.20		5.53	67.47		5.53	67.47			
No.1	No.1 + 0.00		4.25			4.25					
		20.00		3.29	65.80		3.29	65.80			
No.2	No.2 + 0.00		2.32			2.32					
		20.00		2.67	53.40		2.67	53.40			
No.3	No.3 + 0.00		3.02			3.02					
		20.00		2.72	54.40		2.72	54.40			
No.4	No.4 + 0.00		2.42			2.42					
		20.00		2.33	46.60		2.33	46.60			
No.5	No.5 + 0.00		2.24			2.24					
		20.00		2.39	47.80		2.39	47.80			
No.6	No.6 + 0.00		2.53			2.53					
		20.00		2.63	52.60		2.63	52.60			
No.7	No.7 + 0.00		2.73			2.73					
		20.00		2.74	54.80		2.74	54.80			
No.8	No.8 + 0.00		2.75			2.75					
		20.00		2.91	58.20		2.91	58.20			
No.9	No.9 + 0.00		3.07			3.07					
		20.00		3.15	63.00		3.15	63.00			
No.10	No.10 + 0.00		3.22			3.22					
		10.00		2.88	28.80		2.88	28.80			
No.10+10.00	No.10 + 10.00		2.54			2.54					
合計		210.00			631.64			631.64			

構 造 物 撤 去 工 計 算 書						(一式当り)	
構造物取壊し工							
舗装版切断 (アスファルト) (t=15cm以下)	L=	3.12 + 2.54 No. 0、No. 10+10.0	=	5.66	m	5.7	
As取壊し	A=	舗装面積計算書より 631.64	=	631.64	m2	631.6	
運搬処理工							
殻運搬 (As塊)	V=	As取壊しより 631.64 × 0.04	=	25.27	m3	25.3	
殻処分 (As塊)	V=	殻運搬 (As塊) より 25.27	=	25.27	m3	25.3	

区 画 線 工 計 算 書					(一式当り)	
区画線工 消火栓 黄色 実線 W=15cm換算	L= 図面より 4.20 + 4.20 = 8.40				m	8.4

仮 設 工 計 算 書

(一式当り)

交通管理工					
交通誘導警備員	N=	1.00	=	1.00	式
					1.0