

土 工 計 算 書

(一式当り)

掘削	V= 舗装数量より 239.00 × 0.22	= 52.58	m3	52.6
土砂等運搬	V= 掘削より 52.58	= 52.58	m3	52.6

舗 装 工 計 算 書

(一式当り)

路面切削工					
路面切削工 (t=50)	A1=	舗装面積計算書より 1856.00	=	1856.00	
No.4付近 交差点部	A2=	(28.70 + 5.40) × 1/2 × 12.70	=	216.54	
			Σ =	2072.54	m2 2072.5
殻運搬 (路面切削・As)	V=	路面切削工より 2072.54 × 0.05	=	103.63	m3 103.6
殻処分 (As)	V=	殻運搬より 103.63 ※構造物撤去工に計上	=	103.63	
アスファルト舗装工					
下層路盤 (RC-40 t=120)	A=	舗装面積計算書より 239.00	=	239.00	m2 239.0
上層路盤 (M-30 t=100)	A=	舗装面積計算書より 239.00	=	239.00	m2 239.0
表層工 (top13 t=50)	A=	路面切削工、上層路盤より 2072.54 + 239.00	=	2311.54	m2 2311.5

舖				裝				面				積				計				算				書			
測 點 名	測 點			距 離 (m)	表			層			路		面		掘	削	下 層 路 盤 • 上 層 路 盤										
	N0.0	+	0.00		幅 (m)	平 均 (m)	面 積 (m2)	幅 (m)	平 均 (m)	面 積 (m2)	幅 (m)	平 均 (m)	面 積 (m2)														
N0.0	N0.0	+	0.00	7.10													7.10										
N0.1	N0.0	+	20.00	8.20	7.65	153.00											8.20	7.65	153.00								
N0.1+10.00	N0.1	+	10.00	9.00	8.60	86.00	9.00										9.00	8.60	86.00								
	N0.1	+	10.00	10.00	9.50	95.00	10.00	9.50	95.00	10.00	9.50	95.00															
N0.3	N0.2	+	20.00	10.50	10.25	205.00	10.50	10.25	205.00	10.50	10.25	205.00															
N0.4	N0.3	+	20.00	10.40	10.45	209.00	10.40	10.45	209.00	10.40	10.45	209.00															
N0.5	N0.4	+	20.00	9.20	9.80	196.00	9.20	9.80	196.00	9.20	9.80	196.00															
N0.6	N0.5	+	20.00	7.40	8.30	166.00	7.40	8.30	166.00	7.40	8.30	166.00															
N0.7	N0.6	+	20.00	6.60	7.00	140.00	6.60	7.00	140.00	6.60	7.00	140.00															
N0.8	N0.7	+	20.00	8.10	7.35	147.00	8.10	7.35	147.00	8.10	7.35	147.00															
N0.9	N0.8	+	20.00	9.80	8.95	179.00	9.80	8.95	179.00	9.80	8.95	179.00															
N0.10	N0.9	+	20.00	10.30	10.05	201.00	10.30	10.05	201.00	10.30	10.05	201.00															
N0.11	N0.10	+	20.00	7.20	8.75	175.00	7.20	8.75	175.00	7.20	8.75	175.00															
N0.12	N0.11	+	20.00	7.10	7.15	143.00	7.10	7.15	143.00	7.10	7.15	143.00															

区画線工計算書

(一式当り)

区画線工					
外側線 白色 実線 W=150	L1=	図面より 240.00	=	240.00	
中央線 白色 実線 W=150	L2=	図面より 226.00	=	226.00	
			Σ =	466.00	m 466.0
中央線 白色 破線 W=150	L=	図面より 49.00	=	49.00	m 49.0
消火栓 黄色 実線 W=150	L=	図面より 3.60	=	3.60	m 3.6
ゼブラ 白色 実線 W=450	L=	図面より 76.00 (導流帯)	=	76.00	m 76.0
記号等 白色 実線 W=150換算	L=	図面より 86.00 (横断歩道予告、中心点三角、矢印)	=	86.00	m 86.0

構 造 物 撤 去 工 計 算 書

(一式当り)

構造物取壊し工

舗装版切断 (As) (t=15cm以下)	L=	9.00 ※No. 1+10.00横断	=	9.00	m	9.0
-----------------------------	----	------------------------	---	------	---	-----

アスファルト 舗装版取壊し	A=	舗装面積計算書より 239.00	=	239.00	m2	239.0
------------------	----	---------------------	---	--------	----	-------

運搬処理工

殻運搬 (As塊)	V=	アスファルト舗装版取壊しより 239.00 × 0.05	=	11.95	m3	12.0
--------------	----	---------------------------------	---	-------	----	------

殻処分 (As塊)	V=	アスファルト舗装版取壊し・殻運搬（路面切削）より 11.95 + 103.63	=	115.58	m3	115.6
--------------	----	--	---	--------	----	-------

仮 設 工 計 算 書

(一式当り)

交通管理工					
交通誘導警備員	N=	1.00	=	1.00	式
					1.0