

数量計算書

[illegible]

道 路 土 工 計 算 書

(一式当り)

掘削工

掘削

V= 舗装面積計算書より 757.79 × 0.10 = 75.78 m3 75.8

残土処理工

土砂等運搬

V= 掘削より 75.78 = 75.78 m3 75.8

構造物撤去工計算書

(一式当り)

構造物取壊し工						
舗装版切断 (アスファルト) (t=15cm以下)	L=	4.50 + 3.80 + 10.30 ※No. 0横断：4.50m、No. 9+2.50横断：3.80m、 No. 8付近交差部：10.30m	=	18.60	m	18.6
舗装版取壊し (アスファルト) (t=10cm以下)	A=	取壊し数量計算書より 757.79	=	757.79	m2	757.8
運搬処理工						
殻運搬 (アスファルト)	V=	舗装版取壊しより 757.79 × 0.04	=	30.31	m3	30.3
殻処分 (アスファルト)	V=	殻運搬より 30.31	=	30.31	m3	30.3

取 壊 し 数 量 計 算 書													
測 点 名	測 点			距 離 (m)	ア ス フ ァ ル ト 舗 装								
					幅 (m)	平 均 (m)	面 積 (m2)	幅 (m)	平 均 (m)	面 積 (m2)	断 面 積 (m2)	平 均 (m2)	体 積 (m3)
NO. 0	NO. 0	+	0. 00	0. 00	4. 50								
NO. 1	NO. 0	+	20. 00	20. 00	4. 64	4. 57	91. 40						
NO. 2	NO. 1	+	20. 00	20. 00	4. 10	4. 37	87. 40						
NO. 3	NO. 2	+	20. 00	20. 00	4. 46	4. 28	85. 60						
NO. 4	NO. 3	+	20. 00	20. 00	4. 07	4. 27	85. 40						
NO. 5	NO. 4	+	20. 00	20. 00	3. 40	3. 74	74. 80						
NO. 6	NO. 5	+	20. 00	20. 00	3. 80	3. 60	72. 00						
NO. 7	NO. 6	+	20. 00	20. 00	4. 27	4. 04	80. 80						
NO. 8	NO. 7	+	20. 00	20. 00	4. 39	4. 33	86. 60						
NO. 8+15. 4	NO. 8	+	15. 40	15. 40	3. 94	4. 17	64. 22						
NO. 8+15. 4	NO. 8	+	15. 40	0. 00	4. 74								
NO. 9	NO. 8	+	20. 00	4. 60	3. 91	4. 33	19. 92						
NO. 9+2. 5	NO. 9	+	2. 50	2. 50	3. 80	3. 86	9. 65						
合計				182. 50			757. 79						

舗 装 工 計 算 書

(一式当り)

アスファルト舗装工

上層路盤 (M-30, t=100mm)	A=	舗装面積計算書より 757.79	=	757.79	m2	757.8
表層 (top13, t=40mm)	A=	舗装面積計算書より 757.79	=	757.79	m2	757.8

舖 装 面 積 計 算 書													
測 点 名	測 点			距 離 (m)	表 層			上 層 路 盤			幅 平 均 面 積 (m) (m) (m2)		
					幅 (m)	平 均 (m)	面 積 (m2)	幅 (m)	平 均 (m)	面 積 (m2)			
NO. 0	NO. 0	+	0. 00	0. 00	4. 50			4. 50					
NO. 1	NO. 0	+	20. 00	20. 00	4. 64	4. 57	91. 40	4. 64	4. 57	91. 40			
NO. 2	NO. 1	+	20. 00	20. 00	4. 10	4. 37	87. 40	4. 10	4. 37	87. 40			
NO. 3	NO. 2	+	20. 00	20. 00	4. 46	4. 28	85. 60	4. 46	4. 28	85. 60			
NO. 4	NO. 3	+	20. 00	20. 00	4. 07	4. 27	85. 40	4. 07	4. 27	85. 40			
NO. 5	NO. 4	+	20. 00	20. 00	3. 40	3. 74	74. 80	3. 40	3. 74	74. 80			
NO. 6	NO. 5	+	20. 00	20. 00	3. 80	3. 60	72. 00	3. 80	3. 60	72. 00			
NO. 7	NO. 6	+	20. 00	20. 00	4. 27	4. 04	80. 80	4. 27	4. 04	80. 80			
NO. 8	NO. 7	+	20. 00	20. 00	4. 39	4. 33	86. 60	4. 39	4. 33	86. 60			
NO. 8+15. 4	NO. 8	+	15. 40	15. 40	3. 94	4. 17	64. 22	3. 94	4. 17	64. 22			
NO. 8+15. 4	NO. 8	+	15. 40	0. 00	4. 74			4. 74					
NO. 9	NO. 8	+	20. 00	4. 60	3. 91	4. 33	19. 92	3. 91	4. 33	19. 92			
NO. 9+2. 5	NO. 9	+	2. 50	2. 50	3. 80	3. 86	9. 65	3. 80	3. 86	9. 65			
合計				182. 50			757. 79			757. 79			

